

- A. AIA Document A201 “General Conditions of the Contract for Construction”, 1997 Edition, is hereby made a part of these Conditions to the Contract to the same extent as if bound herein.

IV. SCOPE OF WORK

The scope of work shall include, but not be limited to, the following:

1. Contractor to furnish all supervision, labor, materials and equipment to install the work as detailed on the contract documents and provide a turnkey installation.
2. Contractor is to provide full time job site superintendent to coordinate all architectural finishes, mechanical, sprinkler, electrical and all other work.
3. General Conditions – Contractor will be responsible for providing the following:
 - Daily clean up of work area to include hourly task clean-up when required.
 - Temporary toilets and dumpsters at designated location on-site to include (at a minimum) cones to block off construction staging from pedestrian parking.
 - Final cleaning.
 - Temporary protection of existing and newly installed finishes including elevator cabs, doors, corridor walls, etc.
4. Contractor to provide all demolition as required.
5. Contractor is to protect all existing finishes throughout the duration of the project. Existing Conditions photos shall be recorded prior to commencement of work. Contractor to repair/replace any item that becomes damaged.
6. Contractor to furnish and install studs, insulation, drywall and finishing, including patching rated walls after utility installation.
7. Contractor to furnish and install all painting and wall finishes.
8. Contractor to provide a painting allowance of (2) days to touch-up finishes after the tenant move-in.
9. Contractor to furnish and install all rough, blocking, finish carpentry.
10. Contractor to furnish and install all doors and hardware.
11. Contractor to furnish and install security bars and access doors as may be required.
12. Contractor is responsible for all keying and coordinating keying with building/floor master
13. Contractor to install all fire-safing and patching as may be required.
14. Flooring Contractor to prep, flash, level, and install new floor finishes per manufacturer requirements. Finishes are specified within the construction documents.
15. Contractor to furnish and install plumbing including insulation, floor cut, and patch as required.
16. Contractor to furnish and install temporary lighting on the floor and temporary power for subcontractor use if required.
17. Contractor to salvage and return all existing light fixtures to the landlord.
18. Contractor to furnish and install all lighting.
19. Contractor shall provide the electrical system complete to all points of connection and services as shown on the drawings.
20. Contractor to furnish and install new panels and circuit breakers as required.
21. Contractor to furnish all power wiring.

22. A label shall be permanently affixed to all receptacles and shall identify the branch circuit information (panel/breaker). Furnished by the contractor.
23. Provide professional, typed written panel board schedules including circuit use, suite or room number.
24. Contractor to provide final electrical connection to systems furniture supplied by the tenant.
25. Contractor will be responsible for obtaining all Trade permits; and, payment of all permit and inspection fees. Owner has applied for the AHJ Building Permit.
26. Contractor will comply with all state and local codes.
27. Contractor will be responsible for all testing, field layout, and certification as required.
28. At completion of project, contractor shall submit complete “as-built” drawings and O&M manuals. Two physical copies of the “as-built” drawings are required and shall be complete and of good quality. Two sets of O&M manuals are required and shall be supplied in a binder(s) with appropriate section dividers and a section page that completely identifies the equipment. The manuals shall contain, at a minimum: a) warranty letter and information, b) list of all subcontractors used, c) submittals, RFIs, meeting minutes, schedules d) electrical, mechanical, plumbing, and fire alarm detail information, e) HVAC system and control information to include Testing & Balancing Report.
29. Contractor is responsible for reviewing Architectural Plans to make sure installation corresponds with the plans and is coordinated with the work of other subcontractors.
30. Contractor will coordinate installation with other trades with regards to schedule and to prevent interference.
31. Provide coordination for all subcontractors even if others are holding the contract.
32. Contractor shall furnish all necessary submittals and cut-sheets for approval as soon as possible after contract is awarded. **Contractor shall furnish the submittals for the Roof Top Unit (RTU) within 5 days of the notice to proceed.**
33. Contractor agrees to provide sufficient manpower, materials and equipment to support the scheduled occupancy.
34. Contractor will be diligent in their efforts to provide a safe and clean pathway to all exits and corridors.
35. Provide and maintain a complete construction schedule.
36. Contractor to furnish and install all interior blinds.
37. Contractor shall protect and clean all existing perimeter blinds.
38. Contractor shall inspect and test all new and existing HVAC equipment.
39. Contractor to provide a certified air balance of the system including report.
40. Contractor to furnish and install HVAC modifications as defined on the construction documents including all controls.
41. Contractor to start-up and test all systems with new filters.
42. Contractor to provide power to all equipment including new/relocated VAV boxes, exhaust fans, water heaters, etc.
43. Contractor to provide all rigging/hoisting equipment for any equipment that requires it. Contractor to furnish and provide a staging plan for all rigging/hoisting equipment prior to equipment delivery to the site.
44. All roof-mounted equipment must be on curbs, 8” high at a minimum.

45. Contractor is responsible for all roof penetrations, cutting, blocking, flashing, supports, etc.
46. Contractor to design, furnish and install required modifications to the fire alarm system, including any modification to the enunciator panel.
47. Contractor to provide design, permitting and modification of existing sprinkler system if required.
48. Contractor to furnish and install the emergency exit and lighting system.
49. Contractor will be responsible for start-up and inspection of complete electrical system.
50. Card readers will be installed by tenant, contractor to provide power to card reader locations.
51. Preferred Roofing Vendor – F.A. Taylor & Son.
52. Fire Alarm Tie-in Vendor – Fireline
53. Contractor to furnish and install power for on-building signage (photocell on/timeclock off) above the second-floor ceiling for the tenant's sign vendor.
54. Contractor to furnish and install an additional automatic operator at the exterior suite entry door to include, door hardware, accessory buttons, power, tie-in, etc.
55. Contractor to furnish and install power and electronic hardware at all openings receiving card readers.
- 56. The Owner has procured the Roof Top Unit and associated curbs due to lengthy lead times. The unit will be shipped to the Contractor's designated location for Contractor delivery to the site and installation.**

V. PRICING ALTERNATES & BREAK OUTS:

Break Out Pricing #01 - Extension of the Public Corridor (including the following, but not limited to)

- a. Doors: (1 ea.) suite entry door
- b. Drywall: framing, hanging, and finishing (corridor side)
- c. Ceilings: grid and tile
- d. Flooring: carpet tile and base
- e. Painting: walls and frames (corridor side)
- f. Sprinkler: modify heads as required
- g. Mechanical: connections and diffusers
- h. Electrical: power, devices, and lighting

*****Refer to Exhibit A for further information***

Alternate #01 – Performance Bond dollar value & percentage

Alternate #02 – Builders Risk Insurance dollar value & percentage

Alternate #03 – Electric Hand Driers in Restrooms lieu of paper towel dispensers

Ded. Alternate #04 – Installation of non-medical grade receptacles

Ded. Alternate #05 – Low Voltage Cabling (Note #6 / E-201)

Ded. Alternate #06 – Remove Light Fixtures D & E